

## Auditing Test Report

Test Report No. 258816/26

Date: 21/07/2024

### Client

Saudi Vitrified Clay Pipe Co.

P.O. Box 6415

Riyadh 11442

Kingdom of Saudi Arabia

Sampling Date: 17/07/2024

Test Date: 18/07/2024

### Auditing Purpose:

Testing of Vitrified Clay Pipes jointed by system C according to EN 295-1:2013

### Size Description:

Nominal Size: DN 300 \* 2000 mm

Jointing System: System C

Class: 160 - Class B

### Description of Sampling

Samples were collected randomly from the stock at the client's manufacturing works in Riyadh (Kingdom of Saudi Arabia) by the agent of the Suhaimi - Fugro

### Underlying specification /description of the tests

EN 295-1:2013 "Vitrified clay pipe systems for drains and sewers - Part 1: Requirements for pipes, fittings & joints"

GSO EN 295-1:2008 "Vitrified clay pipe systems for drains and sewers - Part 1: Requirements for pipes, fittings & joints"

EN 295-2:2013 "Vitrified clay pipe systems for drains and sewers - Part 2: Evaluation of conformity and sampling"

EN 295-3:2012 "Vitrified clay pipe systems for drains and sewers - Part 3: Test Methods"



Test Results of DN 300 SS - Class B

Test Report No. 258816/26

	Test Type		Unit	Sample 1	Sample 2	Sample 3	Req.	Result
	Pipes	Marking (visual Inspection)		-	✓	✓	✓	✓
Crushing Strength		KN/m	62	59	63	≥ 55	✓	
Internal Barrel Diameter "D1"		mm	301	303	299	≥ 293	✓	
Length		mm	2010	2015	2010	2000 <sup>+4%</sup> <sub>-1%</sub>	✓	
Water Tightness		L/m <sup>2</sup>	0.01	0.02	0.02	≤ 0.04	✓	
Deviation from Straightness		mm	1.6	1.1	1.5	< 4.0	✓	
Squareness of Ends		Socket	mm	2.3	2.4	2.2	< 6.0	✓
		Spigot	mm	2.2	2.5	1.9		
Airtightness		mm	0	10	10	Drops ≤ 25	✓	
Chemical Resistance		%	0.15	0.12	0.15	0.10-0.25%	✓	
Water Absorption		%	3.2	3.4	3.2	≤ 6 %	✓	
Joint Assembly	Joint Interchangeability (D4)		mm	371.7	371.5	371.6	371.5 ± 0.5	✓
	Watertightness under Angular Deflection		0.5 bar	No leak, Deflection applied is 30 mm/m for 5 min.			No visible leakage	✓
	Watertightness under Shear		0.5 bar	No leak, Shear force applied is 7.5 KN for 15 min.			No visible leakage	✓
	Continuity of Invert		mm	1.5	1.7	1.4	≤ 4	✓

FUGRO - SUHAIMI LTD

Mohammad Afaq

